

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 065-01806 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Gore Oil Company KCC License #: 5552
(Owner / Company Name) (Operator's)

Address: P.O. Box 2757 City: Wichita

State: KS Zip Code: 67201-2757 Contact Phone: (316) 263 - 3535

Lease: Zeigler Well #: 3 Sec. 35 Twp. 10 S. R. 21 East West

W/2 - SE - NW - Spot Location / QQQQ County: Graham

3300 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3630 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 215' Cemented with: 125 Sacks

Production Casing Size: 5 1/2" Set at: 3681.5' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3373-75'; 3457-59'; 3532-35'; 3568-71'

Elevation: 2103 (G.L. / K.B.) T.D.: 3682' PBTD: _____ Anhydrite Depth: 1565'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC Agent's instructions.

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

FEB 27 2008

If not explain why? _____
CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lenny Dinkel

Phone: (785) 259 - 1928

Address: 2221 Felton City / State: Hays, KS 67601

Plugging Contractor: Swift Services, Inc. KCC License #: 32382
(Company Name) (Contractor's)

Address: P.O. Box 466, Ness City, KS 67560-0466 Phone: (785) 798 - 2300

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-25-08 Authorized Operator / Agent: Lenny M. Dinkel (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Log Bureau April 14, 1954

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore - Veeder Supply Co. Farm Zeigler No. 3 Depth 3682'
 Contractor Veeder Supply & Dev. Co. Pipe 213' 8 5/8" csg. cemented w/125 sacks
3681 1/2' 5 1/2" csg. Cemented w/125 sacks cement
 Location S/4 NW/4 Sec. 35 Twp. 10 Range 21
 Commenced 3-20-54 Completed 3-28-54 County Graham State Kansas

Elevation 2103 KB
Potential: 446

| | | | |
|------------------------|------|------|-----|
| Soil | 0 | 35 | 35 |
| Shale, sand | 35 | 70 | 35 |
| Shale | 70 | 212 | 142 |
| Shale, shells | 212 | 970 | 758 |
| Sand, shale | 970 | 1300 | 330 |
| Shale, shells, red bed | 1300 | 1505 | 205 |
| Shale, shells | 1505 | 1565 | 60 |
| Anhydrite | 1565 | 1606 | 41 |
| Shale, shells | 1606 | 1895 | 289 |
| Shale | 1895 | 2060 | 165 |
| Shale, shells, salt | 2060 | 2275 | 215 |
| Shale, lime | 2275 | 3220 | 945 |
| Lime | 3220 | 3292 | 72 |
| Lime, shale | 3292 | 3375 | 83 |
| Lime | 3375 | 3645 | 270 |
| Lime, shale | 3645 | 3654 | 9 |
| Conglomerate | 3654 | 3680 | 26 |
| Arb. lime | 3680 | 3682 | 2 |
| Total Depth | 3682 | | |

TOPS:

| | |
|--------------|------|
| Topeka | 3126 |
| Heebner | 3333 |
| Toronto | 3355 |
| Lansing | 3373 |
| Conglomerate | 3654 |
| Arbuckle | 3680 |

3682
2103
1579

RECEIVED
KANSAS CORPORATION COMMISSION

FFR 27 2000



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

GORE OIL COMPANY
202 S ST FRANCIS
PO BOX 2757
WICHITA, KS 67202-4518

March 05, 2008

Re: ZEIGLER #3
API 15-065-01806-00-00
35-10S-21W, 3300 FSL 3630 FEL
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550