

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

COPY

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 025212880000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 5-11-2005.

Well Operator: High Bluff Operating, LLC (Owner / Company Name) KCC License #: 33884 (Operator's)

Address: 730 17th St., Suite 700 City: Denver

State: CO Zip Code: 80202 Contact Phone: (303) 295 - 2223

Lease: Goodnight Well #: 1 Sec. 10 Twp. 23N S. R. 25 East West

center - SE/4 - SE/4 - NE/4 Spot Location / QQQQ County: Clark

2240' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

400' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 120' Cemented with: 50 Sacks

Surface Casing Size: 8 5/8" Set at: 719' Cemented with: 400 Sacks

Production Casing Size: 4.5" Set at: 5895' Cemented with: 360 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5604-5610 and 5592-5600

Elevation: 2035' (G.L. / K.B.) T.D.: 5920' P.B.T.D.: _____ Anhydrite Depth: _____

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): Set a cast iron bridge plug at 5450' and 2 sacks of cement on top of plug. Cut casing off at 4700'. 15 gallons of gel water and 50 sacks of cement at 1200' after pull casing. 50 sacks of cement at 700' and 40 sacks at 300' 10 sacks at top of wellhead.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mr. K.O. (Shine) Overby
Employee of High Bluff Operating, LLC

Address: 730 17th St., Suite 700 Phone: (303) 295 - 2223
City / State: Denver, CO

Plugging Contractor: Allied Cement CO., Inc. KCC License #: N/A 99996
(Company Name) (Contractor's)

Address: P.O. Box 31, Russel KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): Will inform Commission 24 hours to plugging, but possibly as early as 2-29-08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-26-08 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202