

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 151-21936-~~15~~ 100-02 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 06/30/1989.

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056
(Owner / Company Name) (Operator's)

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: HISKETT "B" OWWO Well #: 3-23 Sec. 23 Twp. 29 S. R. 11 East West

C - SW - NW - NW Spot Location / QQQQ County: PRATT

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 12 1/4" Set at: 281' KB Cemented with: 200 Sacks

Production Casing Size: 7 7/8" Set at: 4465' KB Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS. 2332'-2338' COUNCIL GROVE
CIBP@2348

Elevation: 1788' (G.L. / K.B.) T.D.: 4532' PBTD: 2348' Anhydrite Depth: 1642'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008

CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Phone: (620) 793 - 0915

Address: P.O. BOX 158 City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925
(Company Name) (Contractor's)

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/24/2008 Authorized Operator / Agent: ADAM T. THORNE
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HISKETT "B" #3-23
Located: SW NW NW, Section 23-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 20, 1989

COMPLETED: June 27, 1989

TOTAL DEPTH: 4690'

LOG

0 - 70 Surface Soil and Sand
70 - 286 Shale and Clay
286 - 1005 Shale
1005 - 1642 Shale and Lime
1642 - 1655 Anhydrite
1655 - 4690 Lime and Shale

CASING RECORD

Ran 7 joints 8 5/8" Casing. 269.70'
pipe set at 281' K.B. Cemented with
200 sacks 60/40 Pozmix, 2% gel and
3% cc. Plug down at 12:15 PM, 6-20-89,
by Howco.

Plugged.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1° at 2690'
1 1/4° at 4658'



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

March 05, 2008

Re: HISKETT B OWWO #3-23
API 15-151-21936-00-02
23-29S-11W, 990 FNL 330 FWL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888