

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 101-21706-60-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 7/02/95.

Well Operator: White & Ellis Drilling, Inc. KCC License #: 5420
(Owner / Company Name) (Operator's)

Address: PO Box 48848 City: Wichita

State: KS Zip Code: 67201-8848 Contact Phone: (316) 321 - 0550

Lease: Clark Well #: 1-15 Sec. 15 Twp. 19 S. R. 29 East West

SW - SE - NW - Spot Location / QQQQ County: Lane

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 3630 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)
KCC-Dig

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 268' Cemented with: 165 Sacks

Production Casing Size: 4 1/2" Set at: 4622' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 4268 to 4270 w/4SPF
4 1/2" csg also cemented w/ Port Collar at 2117 w/ 175 sx

Elevation: 2827 (G.L. / K.B.) T.D.: 4622 PBDT: 4600 Anhydrite Depth: 2161
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per: KCC instructions

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 25 2008
CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dallas Flowers

Address: PO Box 48848 Phone: (316) 321 - 0550

City / State: Wichita, KS 67201-8848

Plugging Contractor: Whitetail Crude Inc. KCC License #: 31627

Address: PO Box 544, Ness City, KS 67560-0544 Phone: (785) 798 - 3641
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 2/25/08

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 2-11-08 Authorized Operator / Agent: Dallas Flowers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DUNNE OIL CO
WICHITA KS 67202

15-19S-29W
SW SE NW

1-15 CLARK

site: 5 S & 2-1/4 W OF DIGHTON KS

cy: LANE

API 15-101-21706

contr: WHITE & ELLIS #9

field: CLEVE

geol: RAUL BRITO

fr
date 06/22/95

spd
date 06/26/95

drig
comp 07/02/95

card
issued 10/30/95

last
revised 10/30/95

ELV: 2832 KB, 2827 GL LOG

tops.....	depth/ datum
ANH.....	.2161 + 671
B/ANH.....	.2187 + 645
HEEB.....	.3944 -1112
LANS.....	.3986 -1154
MUN CR.....	.4168 -1336
STARK.....	.4274 -1442
BKC.....	.4355 -1523
MARM.....	.4395 -1563
PAW.....	.4470 -1638
FT SC.....	.4517 -1685
CHER.....	.4541 -1709
MISS.....	.4609 -1777
RTD.....	.4622 -1790

IP status:

OIL, P 25 BO & 120 BWPD, LKC 4268-4271 ,
, 10/10/95

LTD.....4623 -1791

CSG: 8-5/8" 268 / 165 SX (ALT 2), 4-1/2" 4622 / 75 SX,
PORT COLLAR AT 2117 / 175 SX

COMMENT: LOST CIRC AT 2978

NO CORES.

DST (1) 4168-4195 (LANS 140), / 30-45-60-60, REC 5'
CLEAN OIL, 85' SLI OCM (2% OIL, 98% M, CHL 1500
PPM) ISIP 816# FSIP 714# IFP 40# -48# FFP 73# -78#
BHT 112'

COPYRIGHT 1995
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 25 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WHITE & ELLIS DRILLING, INC.
PO BOX 48848
WICHITA, KS 67201-8848

March 05, 2008

Re: CLARK #1-15
API 15-101-21706-00-00
15-19S-29W, 2970 FSL 3630 FEL
LANE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888