

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled  
CONSERVATION DIVISION  
WICHITA, KS

API # 15 - 051-04993 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: Delta Petroleum Corporation KCC License #: 33250

Address: 370 17th Street, Suite 4300 City: Denver

State: CO Zip Code: 80202 Contact Phone: (303) 575 - 0397

Lease: B. Braun, RAY Well #: A 1 Sec. 2 Twp. 14S S. R. 17W  East  West

NE - NW - NW Spot Location / QQQQ County: Ellis

380' 4985 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

980' 4406 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

Surface Casing Size: 8-5/8" Set at: 1,116' Cemented with: 300 Sacks

Production Casing Size: 5-1/2" Set at: 3,454' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open Hole

Elevation: 1927' ( G.L. /  K.B.) T.D.: 3456' PBTD: N/A Anhydrite Depth: 1108'

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): Please see attached proposal

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? This well was spud on November 5th, 1944 and was completed on December 7th, 1944. PI/Dwights and KGS do not have any data for a completion rpt. or well logs. Delta acquired the lease on 8/06/2003.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gregg Randall

Phone: (303) 820 - 0154

Address: 370 17th Street, Suite 4300 City / State: Denver, CO 80202

Plugging Contractor: Not determined at this time - Express Well KCC License #: 6426

Address: \_\_\_\_\_ Phone: ( ) - \_\_\_\_\_

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/25/08 Authorized Operator / Agent: Kate Shirley (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Ray Braun 1 or Braun A 1- P&A Procedure

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 26 2008

CONSERVATION DIVISION  
WICHITA, KS

February 20, 2008

- 1) RU. Remove production equipment.
- 2) RIH with tubing to bottom at 3,456'. Pump cement from 3,456' to 3,200'.
- 3) Circulate hole with mud laden fluid.
- 4) Perforate at 1,115'. PU and set CICR at 1,075'. Establish injection and pump 50 sacks of cement. Dump 20' of cement on top of CICR.
- 5) Set 50' of cement at surface.
- 6) Cut both casing string off between 4' and 10' below the ground level and weld on steel cap. Place marker.
- 7) Reclaim the site and reseed.

**DELTA**  
**PETROLEUM CORPORATION**

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 26 2008

370 SEVENTEENTH ST.  
SUITE 4300  
DENVER, CO 80202  
(303) 293-9133/TEL  
(303) 298-8251/FAX

CONSERVATION DIVISION  
WICHITA, KS

February 25, 2008

Richard Williams  
Kansas Conservation Division  
District Office # 4  
2301 E. 13<sup>th</sup> Street  
Hays, KS 67601-2651


RE: Ray Braun 1 2-14S-17W, NENWNW Ellis County  
K.A.R. 82-3-111 Temporary Abandonment, penalty, plugging

Mr. Williams,

Delta Petroleum Corporation is going to plug the above mentioned well. I have attached the CP-1 form and the proposed method of plugging the well for your records. I have sent the original form to the Wichita office. I would be happy to answer any questions that you might have with this data.

Sincerely,

Delta Petroleum Corporation



Kate Shirley  
Regulatory Technician  
[Kshirley@deltapetro.com](mailto:Kshirley@deltapetro.com)  
(303) 575-0397

Cc: Deanna Garrison- Wichita office

/ks



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

DELTA PETROLEUM CORPORATION  
370 17TH ST STE 4300  
DENVER, CO 80202-5632

March 05, 2008

Re: RAY BRAUN A #1  
API 15-051-04993-00-00  
2-14S-17W, 4985 FSL 4406 FEL  
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550