

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 151-21,683 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 08/23/85 SPUD.

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056  
(Owner / Company Name) (Operator's)

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: ( 316 ) 684 - 8481

Lease: HISKETT "B" Well #: 1-23 Sec. 23 Twp. 29 S. R. 11  East  West

- NW - NE - NW Spot Location / QQQQ County: PRATT

380 4950 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 3630 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)  
*per oper - KCC - Dlg*

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: NONE Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 255' KB Cemented with: 210 Sacks

Production Casing Size: 4 1/2" Set at: 4744' KB Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS. 2332'-2338' COUNCIL GROVE

CIBP@2348

Elevation: 1786' ( G.L. /  K.B.) T.D.: 4750' P.B.T.D.: 2731' Anhydrite Depth: 1642' ES  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 28 2008

CONSERVATION DIVISION  
WICHITA, KS

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Address: P.O. BOX 158 Phone: ( 620 ) 793 - 0915

City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925  
(Company Name) (Contractor's)

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: ( 620 ) 727 - 3410

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent Adam T. Thorne

Date: 2/24/2008 Authorized Operator / Agent: ADAM T. THORNE  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HISKETT "B" 1-23  
Located: NW NE NW, Section 23-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 23, 1985

COMPLETED: September 2, 1985

TOTAL DEPTH: 4750'

## LOG

0 - 70 Surface Soil and Sand  
70 - 288 Shale, Red Bed  
288 - 1150 Shale, Sand, Red Bed  
1150 - 1800 Shale and Lime Str.  
1800 - 4030 Lime and Shale  
4030 - 4305 Lime  
4305 - 4630 Lime and Shale  
4630 - 4750 Lime

## CASING RECORD

Ran 6 joints new 8 5/8", 24# casing.  
242.72' pipe set at 255' K.B. Cemented  
with 210 sasks 60/40 Pozmix, plug 3% cc.  
Plug down at 3:30 PM, 8-23-85, by Howco.

Ran 116 joints 4 1/2", 10.5# casing.  
13 joints were used. 4735.07' pipe  
set at 4744' K.B. Cemented with 100  
sacks Lite and 125 sacks 50/50 Pozmix  
plus our regular additives and flush  
ahead. Plug down at 2:30 PM, 9-2-85,  
by Howco. Plugged rathole.

Deviation Surveys: 1/4° at 1906'  
1/4° at 4105'  
1 1/4° at 4570'

RECEIVED  
STATE OF KANSAS DEPARTMENT OF CONSERVATION

FEB 28 2008

CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

March 05, 2008

Re: HISKETT B #1-23  
API 15-151-21683-00-00  
23-29S-11W, 4950 FSL 3630 FEL  
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888