

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 135 - 21017 - 00 - 01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3/75.

Well Operator: Beren Corp. KCC License #: 5364
(Owner / Company Name) (Operator's)

Address: PO Box 723 City: Hays

State: KS Zip Code: 67601 Contact Phone: (785) 628 - 6101

Lease: Levi Well #: 3 Sec. 10 Twp. 16S S. R. 26 East West

SE - NE - NE - Spot Location / QQQQ County: NESS

_____ Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

_____ Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 281 Cemented with: 200 Sacks

Production Casing Size: 4-1/2 Set at: 4635 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: MISS 4551-53, 4534-39, 4542-46, 4555-58

CSG LEAK: 1630, 2629-44, 1627-1808

Elevation: 2626 (G.L. / K.B.) T.D.: _____ PBDT: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): RUN TBG TO T.D. PUMP 35 SKS 60/40 4% GEL 150# HULLS PULL TBG TO 1500' PMP 40 SKS COMMON W/ 3% CC, LET SET & TEST CSG TO 300 PSI, IF OK PERF AT 1200' PMP CSG VOLUME 60/40 4% & SQUEEZE IN. TIE ONTON 8-5/8 AND PMP 150 SKS 60/40 4%

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 29 2008

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mark Leiker w/ Beren Corp.

Phone: (785) 628 - 6101

Address: PO Box 723 City / State: Hays, KS

Plugging Contractor: H-D Oilfield Services KCC License #: 3297
(Company Name) (Contractor's)

Address: PO Box 87 Bazine, KS 67516 Phone: (785) 398 - 2289

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-25-08 Authorized Operator / Agent: Mark Leiker
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BEREN CORPORATION
PO BOX 20380
WICHITA, KS 67208-1380

March 04, 2008

Re: LEVI OWWO #3
API 15-135-21017-00-01
10-16S-26W, FL FL
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 31, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond

Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888