

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 33344
 Name: Quest Cherokee, LLC
 Address: P O Box 100
 City/State/Zip: Benedict, KS 66714
 Purchaser: Bluestem Pipeline, LLC
 Operator Contact Person: Douglas L. Lamb
 Phone: (620) 698-2250
 Contractor: Name: Barton T. Lorenz
 License: 33286
 Wellsite Geologist: Michael L. Ebers
 Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
 If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>4/14/04</u>	<u>4/15/04</u>	<u>4/22/04</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

**RECEIVED
AUG 25 2004
KCC WICHITA**

API No. 15 - 133-26063-0000
 County: Neosho
 _____ - sw - nw Sec. 19 Twp. 30 S. R. 18 East West
1980 feet from S (N) (circle one) Line of Section
510 feet from E (W) (circle one) Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE SE (NW) SW
 Lease Name: Leck Family Trust Well #: 19-1
 Field Name: Cherokee Basin CBM
 Producing Formation: Summit/Mulky
 Elevation: Ground: 978 Kelly Bushing: n/a
 Total Depth: 1162' Plug Back Total Depth: 1137
 Amount of Surface Pipe Set and Cemented at 21 Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set _____ Feet
 If Alternate II completion, cement circulated from 1137
 feet depth to surface w/ 146 sx cmt.

Drilling Fluid Management Plan Alt. # 2 KGR 6/25/07
 (Data must be collected from the Reserve Pit)
 Chloride content _____ ppm Fluid volume _____ bbls
 Dewatering method used _____
 Location of fluid disposal if hauled offsite: _____
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Douglas L. Lamb
 Title: Manager Date: 8/23/04

Subscribed and sworn to before me this 23rd day of August,
 2004.

Notary Public: Jennifer R. Houston
 Date Commission Expires: July 30, 2005

JENNIFER R. HOUSTON
 Notary Public - State of Kansas
 My Appt. Expires July 30, 2005

KCC Office Use ONLY

Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Quest Cherokee, LLC Lease Name: Leck Family Trust Well #: 19-1
 Sec. 19 Twp. 30 S. R. 18 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)
 List All E. Logs Run:

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
	Name	Top Datum
	Lenapah Lime	340 +637
	Altamont Lime	378 +599
	Pawnee Lime	533 +444
	Oswego Lime	603 +374
	Verdigris Lime	721 +256
	Mississippi Lime	1064 -87

Dual Induction Log
 Compensated Density/Neutron Log
 Gamma Ray/Neutron Log

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	8-5/8"	24.75#	21'	"A"	6sx	
Production	6-3/4"	4-1/2"	10.5#	1137'	"A"	146sx	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	634-639	147sx sand & 495bbbls water	634-639 & 653-659
4	653-659		
RECEIVED AUG 25 2004 KCC WICHITA			

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-3/8"	667'	n/a	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.		Producing Method			
5/26/04		<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
		41.07	28		

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled

Production Interval Other (Specify) _____



CONSOLIDATED
OIL WELL
SERVICES
AN INFINITY COMPANY

TICKET NUMBER **24350**

211 W. 14TH STREET, CHANUTE, KS 66720
620-431-9210 OR 800-467-8676

LOCATION CHANUTE

FIELD TICKET

2004 12 10

DATE	CUSTOMER ACCT #	WELL NAME	QTR/QTR	SECTION	TWP	RGE	COUNTY	FORMATION
4-22-04	6628	LECK FAMILY TRUST 17-1		17	30S	18E	NO	
CHARGE TO <u>QUEST CHEROKEE LLC</u>				OWNER				
MAILING ADDRESS <u>P.O. BOX 100</u>				OPERATOR				
CITY & STATE <u>BENEDICT, KANSAS 66714</u>				CONTRACTOR				

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	UNIT PRICE	TOTAL AMOUNT
5401-40	1-WELL	PUMP CHARGE CEMENT PUMP		472. ⁰⁰
1110	14 SKS	GILSONITE		271. ⁶⁰
1107	1 1/2 SK	CELLOFLAKE-FLO-SEAL		56. ⁶³
1118	2 SKS	PREMIUM GEL - BENTONITE (AHEAD)		23. ⁶⁰
1111B	15 GAL	SODIUM SILICATE		150. ⁰⁰
1215	1 GAL	KCL		22. ⁰²
1123	5460 GAL	CITY WATER (130 BEL)		6143
5407	25 mi	BLENDING & HANDLING TON-MILES <u>MINIMUM</u> STAND BY TIME MILEAGE		190. ⁰⁰
5501	3 1/2 HR	WATER TRANSPORTS		280. ⁰⁰
5502-40	3 1/2 HR	VACUUM TRUCKS FRAC SAND		262. ⁵⁰
1126	138 SKS	CEMENT <u>OWC (146 SKS TOTAL)</u> <u>(OWC, 5th GILSONITE, 1/4th FLO-SEAL)</u>		1559. ⁴⁰
			SALES TAX	133. ⁷³
ESTIMATED TOTAL				3483. ³⁹

RECEIVED
AUG 25 2004
KCC WICHITA

CUSTOMER or AGENTS SIGNATURE _____ CIS FOREMAN TODD A. TINDLE

CUSTOMER or AGENT (PLEASE PRINT) _____ DATE _____

1879879

Ravin 2790

CONSOLIDATED OIL WELL SERVICES, INC.
 211 W. 14TH STREET, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

TICKET NUMBER 31528
 LOCATION CHANUTE
 FOREMAN TODD A. TINDLE

TREATMENT REPORT

DATE	CUSTOMER #	WELL NAME	FORMATION
4-22-04	6628	LECY FAMILY TRUST #1-1	
SECTION	TOWNSHIP	RANGE	COUNTY
19	S05	18E	NO.
CUSTOMER			
QUEST CHEROKEE LLC			
MAILING ADDRESS			
P.O. BOX 100			
CITY			
BENEDICT			
STATE		ZIP CODE	
KANSAS		66714	
TIME ARRIVED ON LOCATION			

TRUCK #	DRIVER	TRUCK #	DRIVER
206	WES		
400	INAC		
289-40	TIM		
428-40	JEFF		

WELL DATA	
HOLE SIZE	6-7/8
PACKER DEPTH	
TOTAL DEPTH	1148'
PERFORATIONS	
SHOTS/FT	
CASING SIZE	4 1/2
OPEN HOLE	
CASING DEPTH	1137
CASING WEIGHT	TUBING SIZE
CASING CONDITION	TUBING DEPTH
	TUBING WEIGHT
	TUBING CONDITION
TREATMENT VIA	

TYPE OF TREATMENT	
<input type="checkbox"/> SURFACE PIPE	<input type="checkbox"/> ACID BREAKDOWN
<input checked="" type="checkbox"/> PRODUCTION CASING	<input type="checkbox"/> ACID STIMULATION
<input checked="" type="checkbox"/> SQUEEZE CEMENT	<input type="checkbox"/> ACID SPOTTING
<input type="checkbox"/> PLUG & ABANDON	<input type="checkbox"/> FRAC
<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> FRAC + NITROGEN
<input type="checkbox"/> MISP. PUMP	<input type="checkbox"/>
<input type="checkbox"/> OTHER	<input type="checkbox"/>

PRESSURE LIMITATIONS		
	THEORETICAL	INSTRUCTED
SURFACE PIPE		
ANNULUS LONG STRING		
TUBING		

INSTRUCTION PRIOR TO JOB CIRCULATE W/ FRESH H₂O; RUN 2 GEL AHEAD; 5 BBL PAD OF H₂O
RUN 11 BBL DYE W/ 15 GAL SODIUM SILICATE IN LAST 5 BBL; CEMENT UNTIL DYE RETURNS;
FLUSH PUMP; PUMP PLUG W/ KCL WATER; SET FLOAT SHOE; WASH DOWN 1 JOINT CASING
 AUTHORIZATION TO PROCEED _____ TITLE CEMENT UNTIL LEAD 12.5; TAIL IN @ DATE

TIME AM / PM	STAGE	BBL'S PUMPED	INJ RATE	PROPPANT PPG	SAND / STAGE	PSI	
							BREAKDOWN PRESSURE
							DISPLACEMENT
							MIX PRESSURE
							MIN PRESSURE
							ISIP
							15 MIN.
							MAX RATE
							MIN RATE

RECEIVED
 AUG 25 2004
 KCC WICHITA

TERMS

In consideration of the prices to be charged for our services, equipment and products as set forth in Consolidated Oil Well Services, Inc's (COWS) current Price Schedule, and for the performance of services and supplying of materials; customer agrees to the following terms and conditions.

Terms. Cash in advance unless satisfactory credit is established. On credit sales, invoices payable to P.O. Box 884, Chanute, KS 66720. Invoices payable within 30 days of invoice date. Charges subjected to interest after 30 days from invoice date. Interest will be charged at Maximum rate allowed by law. In the event it is necessary to employ an attorney to enforce collection of such account, customer agrees pay all collection costs and attorney's fees in the amount of 20% of said amount.

Any applicable federal, state or local sales, use, occupation, consumer's or emergency taxes shall be added to the quoted price.

A sales tax reimbursement of 2% is applied to chemical and product charges for all services performed on oil and gas wells in the State of Texas.

All process license fees required to be paid to others will be added to the scheduled prices.

All prices are subject to change without notice.

SERVICE CONDITIONS

Customer warrants that the well is in proper condition to receive the services, equipment, products, and materials to be supplied by COWS.

"The customer shall at all time have complete care, custody, and control of the well, the drilling and production equipment at the well, and the premises about the well. A responsible representative of the customer shall be present to specify depths, pressures, or materials used for any service which is to be performed."

- (a) COWS shall not be responsible for, and customer shall secure COWS against any liability for damage to property of customer and of the well owner (if different from customer), unless caused by the willful misconduct or gross negligence of COWS, this provision applying to but not limited to sub-surface damage and surface damage arising from subsurface damage.
- (b) Customer shall be responsible for and secure COWS against any liability for reservoir loss or damage, or property damage resulting from sub-surface pressure, losing control of the well and/or a well blowout, unless such loss or damage is caused by the willful misconduct of gross negligence of COWS.

- (c) Customer shall be responsible for and secure COWS against any and all liability of whatsoever nature for damages as a result of a subsurface trespass, or an action in the nature thereof, arising from a service operation performed by COWS hereunder.
- (d) Customer shall be responsible for and secure COWS against any liability for injury to or death of persons, other than employees of COWS, or damage to property (including, but not limited to, injury to the well), or any damages whatsoever, irrespective of cause, growing out of or in any way connected with the use of radioactive material in the well hole, unless such damage shall be caused by the willful misconduct or gross negligence of COWS.
- (e) COWS makes no guarantee of the effectiveness of the products, supplies or materials, nor of the results of any treatment or services.
- (f) Because of the uncertainty of variable well conditions and the necessity of relying on facts and supporting services furnished by others, COWS is unable to guarantee the accuracy of any chart interpretation, research analysis, job recommendation or other data furnished by COWS. COWS personnel will use their best efforts in gathering such information and their best judgment in interpreting it, but customer agrees that COWS shall not be responsible for any damage arising from the use of such information except where due to COWS gross negligence or willful misconduct in the preparation or furnishing of it.

WARRANTIES – LIMITATION OF LIABILITY

COWS warrants only title to the products, supplies and materials and that the same are free from defects in workmanship and materials. **THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED OR MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE.** COWS's liability and customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, supplies or materials on their return to COWS or, at COWS's option, to the allowance to the customer of credit for the cost of such items. In no event, shall COWS be liable for special, incidental, indirect, punitive or consequential damages.

COWS personnel will use their best efforts in gathering such information and their best judgement in interpreting it, but Customer agrees that COWS shall not be liable for and CUSTOMER SHALL INDEMNIFY AGAINST ANY DAMAGED ARISING FROM THE USE OF SUCH INFORMATION, even if such is contributed by the COWS negligence or fault.