

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00714-00-01
Spot: NENENW Sec/Twnshp/Rge: 2-11S-21W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: COOK Well #: 1
County: TREGO Total Vertical Depth: 3654 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		
PROD	5.5	3644	0	w/unknown sxs cmt
SURF	8.625	225	0	w/150 sxs cmt

118.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2008 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel - 1000# hulls.
CIBP at 3600'.
Perf's at 3138' - 3520'. New perfs 2050' - 1575' - 800' - 100'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2008 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3255' - pumped 150 sxs cement with 400# hulls.
Pulled tubing to 1705' - pumped 200 sxs cement with 400# hulls - circulated cement out 5 1/2".
Pulled tubing out - tied onto backside - pumped 40 sxs cement - circulated out 5 1/2".
Hole full.

Perfs:

Top	Bot	Thru	Comments
3547	3553		
3534	3535		
3514	3520		
3493	3496		
3441	3446		
3430	3433		
3393	3399		
3368	3372		
3357	3361		
3138	3144		

INVOICED
DATE 3-5-08
INV. NO. 2008061315

Remarks: SWIFT SERVICE CEMENT-TICKET #13269.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 2008

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

FEB 29 2008

PT

STATE: KANSAS COUNTY: TREGO OWWO 2-11S-21W
FIELD: TRICO FLD(MULTIPAY) NE NE NW
OPER: PEEL GLENN W ESTATE 4950 FSL 2970 FEL SEC
WELL: 1 COOK WELL CLASS: DO ELEV: 2090 KB
API: 15-195-00714-0001 STATUS: OIL-WO 2085 GR
SPUD: 06/06/90 COMP: 06/14/90
DTD: 3651 LTD: FTD: ARBUCKLE PBT: BHT:

LOC:

IP: COMP 6/14/90, IPP 14 BO, 160 BWPD PROD ZONE- TOPEKA 3138-3144 LANSING-KC
3357-3553 GROSS ARBUCKLE 3644-3651 OPENHOLE COMMINGLED FIRST REPORT &
COMPLETION

OWWO: TBG: 2 7/8 @ 3600; DRLG COMP 06/08/90 RIG REL 06/08/90
OWWO: OLD INFO: FORMERLY PEEL-HARDMAN 1 COOK. SPUD 10/16/54. 8 @ 225 W/150 SX, 5
1/2 @ 3644 W/CMT. LOG TOPS: TOPEKA 3107, LANSING 3356, ARBUCKLE 3642. OTD 3651.
COMP 12/1/54. IPF 91 BOPD. PROD ZONE: ARBUCKLE 3641-3651 OPENHOLE
PERFS: PERF (LANSING-KANSAS CITY), 3357-3361, 3368-3372, 3393-3399, 3430-3433, 3441-3445,
3493-3496, 3514-3520, 3531-3535, 3547-3553, ACID W/7000 GALS. , PERF (TOPEKA)
3138-3144, ACID W/1000 GALS. ,
PRODUCING INTERVAL: PERF (TOPEKA) 3138-3144,(ARBUCKLE) 3644-3651 OPENHOLE , PERF
(LANSING-KANSAS CITY) 3357-3553 GROSS, NO NEW TREATMENT - ARBUCKLE

OPER ADD: BOX 429, NEWKIRK, OK, 74647 PHONE (405) 362-2368;
CONTR: NOT RPTD