

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00736-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 2-11S-21W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: COOK Well #: 12  
County: TREGO Total Vertical Depth: 3540 feet

Operator License No.: 9090  
Op Name: CHARTER ENERGY, INC.  
Address: PO BOX 252  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3538	0	100 SX
SURF	8.625	165	0	w/unknown sxs cmt <u>115.05</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/26/2008 11:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 623-1861

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel - 1000# hulls.  
PBTD 3515'. Bridge in hole at 3270'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/26/2008 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3225' - pumped 150 sxs cement with 400# hulls.  
Pulled tubing to 1500' - pumped 170 sxs cement with 450# hulls - good circulation of cement.  
Pulled tubing out and topped off with 55 sxs cement - casing full.  
Tied onto backside - pressured up to 200# P.S.I. - shut in.

Perfs:

Top	Bot	Thru	Comments
3440	3443		
3429	3433		
3419	3425		
3381	3389		
3344	3350		

**INVOICED**

DATE 3-5-08

INV. NO. 2008061315

Remarks: SWIFT CEMENTING SERVICE-TICKET #13268.

Plugged through: TBG

District: 04

Signed [Signature]

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 03 2008

CONSERVATION DIVISION  
WICHITA, KS

FEB 29 2008

[Signature]


PEEL-HARDMAN #12 COOK 2-11-21W  
 (TWIN TO #8) W2 W2 NW  
 Contr. PEEL BROS TREGO County  
 E 2085RB Comm. Comp. 7-19-57 IP 85 BOPD/LANS  
 PHY POT

Tops	Depth	Datum
ANH	1530	555
TOP	3122	-1037
HEEB	3305	-1220
LANS	3343	-1258
T.D.	3540	-1455

Casing  
 8" 165  
 5" 3539

PERF 3425-43: ACID 2500

WHITE SW POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS