

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27198-00-00
Spot: NENESW Sec/Twnshp/Rgc: 7-24S-14E
2200 feet from S Section Line, 2215 feet from W Section Line
Lease Name: DYE Well #: 45
County: WOODSON Total Vertical Depth: 1714 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 800 W 47TH ST STE # 409
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	40		25 SX

55.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2007 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RANDY BISHOP Company: HAAAS PET., LLC Phone: (816) 531-5922

Proposed Plugging Method: FILLED TO SURFACE WITH CEMENT. PULLED OUT HOLE, TOPPED OFF AND FILLED RAT HOLE WITH CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 12/05/2007 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THIS WELL CONSISTED OF AN UNCASSED BORE. DRILL PIPE WAS RAN TO T.D... 10 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D.. THE PIPE WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PPUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 200'. CEMENT WAS PUPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE PIPE AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

FEB 20 2008 CPT

CHANUTE, KS


INVOICED
DATE 3-5-08
INV. NO. 2008061319

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 29 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Plugged through: DP

District: 03

Signed



(TECHNICIAN)

