

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21349-00-00
Spot: E2NENWNW Sec/Twnshp/Rge: 31-32S-10W
330 feet from N Section Line, 1170 feet from W Section Line
Lease Name: COLEMAN Well #: 1
County: BARBER Total Vertical Depth: 4560 feet

Operator License No.: 3288
Op Name: JODY OIL & GAS CORPORATION
Address: PO BOX 422
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4567	1830	WITH 100 SX CMT
SURF	8.625	245		WITH 200 SX CMT

148.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2008 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4440' WITH 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2008 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4430' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4491	4495		


INVOICED

DATE 3-5-08
INV. NO. 2008061320

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01



Signed

Steve J Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

[Handwritten signature]