

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22214-00-00  
Spot: SESE Sec/Twnshp/Rge: 32-33S-13W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: SPRIGGS Well #: B-1  
County: BARBER Total Vertical Depth: 5000 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4880		162.50
PKR	4.5	4858		
PROD	4.5	4995	1128	WITH 150 SX CMT
SURF	8.625	447		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2008 11:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: BOB MOORHEAD Company: WOOLSEY OPERATING Phone: (316) 267-4379

Proposed Plugging Method: PLUG AT 4748' WITH 300# HULLS & 25 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/08/2008 12:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*JUNK IN HOLE @ 4858'. CASING LEAK @ 3900'.\*\* SPOT 300# HULLS & 25 SX CMT AT 4748' THROUGH TBG. SPOT PLUGS THROUGH 2 3/8" TBG. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4904	4924		
4810	4830		

**INVOICED**  
DATE 3-5-08  
INV. NO. 2008061327

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 03 2008

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3