

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00290-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 7-32S-34W
2303 feet from S Section Line, 2230 feet from E Section Line
Lease Name: PLOWMAN A Well #: 1
County: SEWARD Total Vertical Depth: 2741 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	2741		SLOTTED LINER
PROD 7		2611	0	WITH 750 SX CMT 89.08
SURF	10.75	546		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/18/2008 8:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2008 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 100# HULLS & 40 SX CMT AT 2040'. 1ST PLUG PUMP 40 SX CMT AT 580'.
2/19/08: 2ND PLUG TAG CMT. TOC @ 850'. FILLED HOLE WITH MUD &
PRESSURED CASING TO 100#. 3RD PLUG AT 580' WITH 40 SX CMT. 4TH PLUG AT
40' WITH 10 SX CMT.

Perfs:

INVOICED
DATE 2-28-08
INV. NO. 2008061289

RECEIVED
FEB 25 2008
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED
FEB 20 2008
KCC Dodge City

Signed Jack MacLaskey
(TECHNICIAN)

Form CP-2/3
PKT