

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22074-00-00
Spot: NWSWSESE Sec/Twnshp/Rge: 8-17S-27W
335 feet from S Section Line, 1240 feet from E Section Line
Lease Name: JOHNSON "A" Well #: 1-8
County: LANE Total Vertical Depth: 4675 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 221 N MAIN STE 300 PO BOX 2758
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		WITH 160 SX CMT

151.94

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/18/2008 10:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 02/18/2008 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Perfs:


INVOICED
DATE 2-28-08
INV. NO. 2008061292

RECEIVED
FEB 25 2008
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form CB-25
[Handwritten signature]