

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21591-00-00
Spot: SESENW Sec/Twnshp/Rge: 28-11S-22W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SHAW CREEK UNIT Well #: 2
County: TREGO Total Vertical Depth: 4015 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4005	0	w/1000 sxs cmt
SURF	8.625	300	0	w/180 sxs cmt

130.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2008 3:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 800# hulls.
Dakota 674' - 974'. Anhy. 1791' - 1831'.
Kline #2 - Unitized as Shaw Creek Unit.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2008 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Services RIH with tubing to 3800'.
Swift Services rigged to tubing - pumped 13 sxs gel - followed with 40 sxs 60/40 pozmix with 250# hulls mixed in.
Pulled tubing to 1600'. Swift rigged to tubing - pumped 130 sxs 60/40 pozmix - 4% gel with 525# hulls to circulate cement to surface.
Pulled tubing - rigged to 8 5/8" casing - pumped 5 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 1000#. S.I.P. 200#.
Topped 4 1/2" casing with 15 sxs. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3938	3954		
3592	3815		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 21 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 2/27/08
INV. NO. 2008061283

Remarks: SWIFT SERVICES, INC. - TICKET #13259.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

FEB 19 2008

REACH OIL CORPORATION
3751 EAST DOUGLAS

#2 KLINE

28-11-22W
SE SE NW

WICHITA, KS 67218
COMPANY TOOLS

CTY TREGO


GEOL PAUL MONTOIA

FIELD SHAW CREEK

ELV 2354 KB SPD 9/28/84
2349 GL

CARD ISSUED 11/8/84

IP P 15 80 & 15 BWPD
LKC 3592-3815 OA
MARM 3938-3954 OA



LOG	Tops	Depth/Datum
ANH	1791 + 563
TOP	3360-1006
HEEB	3572-1218
LKC A	3610-1256
LKC B	3649-1295
LKC C	3665-1311
LKC D	3686-1332
LKC E	3698-1344
LKC F	3711-1357
LKC G	3722-1368
LKC H	3750-1396
LKC I	3770-1416
LKC J	3790-1436

API 15-195-21,591

8 5/8 " 300/180SX, 4 1/2 " 4005/1000SX
NO DST'S
MICT - CO, PF (MARM) 3950-54, 3938-44, W/ 2 SPF, FRAC 750G
AC & 40,000# SD, SWB DWN, GSO, PF (LKC) 3812-15, 3789-91,
3771-74, 3698-3700, 3686-89, 3649-53, 3612-15, 3592-95, W/
2 SPF, AC 6700G, SWB DWN, GSO, T&R, POP, P 15 80 & 15
BWPD 10/23/84 COMMINGLED

LKC K 3811-1457
LKC L 3832-1481
BKC 3850-1496
MARM 3930-1576
PBD 3982-1628
RTD 4015-1661

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS