

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-04952-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 22-11S-18W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HENDERSON E Well #: 5  
County: ELLIS Total Vertical Depth: 3580 feet

Operator License No.: 33306  
Op Name: BLAKE EXPLORATION, LLC  
Address: 201 S. MAIN PO BOX 150  
BOGUE, KS 67625

| String | Size  | Depth (ft) | Pulled (ft) | Comments          |
|--------|-------|------------|-------------|-------------------|
| PROD   | 5.5   | 3582       | 0           | w/unknown sxs cmt |
| SURF   | 8.625 | 1273       | 0           | w/unknown sxs cmt |

**\$ 116.35**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2007 12:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: MIKE DAVIGNON Company: BLAKE EXPLORATION, LLC Phone: (785) 216-0062

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 12 sxs gel spacer.  
RB plug at 3080' with two sxs sand on top.  
Squeezed casing leak 2349' - 2800' w/265 sxs.  
Drilled out to 2705' - got out of pipe.  
Squeezed with 450 sxs. Drilled to 2740' - got out of pipe.  
Decided to P/A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/28/2007 2:45 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated Anhy at 1275' - Dakota at 650'.  
Ran tubing to 2780'. Quality Oil Well Cementing pumped 12 sxs gel spacer, followed with 20 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1275'. Quality Oil Well Cementing pumped 130 sxs 60/40 pozmix - 4% gel - circulated out 5 1/2" casing.  
PTOH. Quality Oil Well Cementing pumped 25 sxs 60/40 pozmix - 4% gel down 5 1/2" casing - circulated cement out 8 5/8". Shut in 8 5/8".  
Max. P.S.I. 500#. S.I.P. 500#.

**Perfs:**

**INVOICED**  
DATE 9-10-07  
INV. NO. 2008060356

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 04 2007

CONSERVATION DIVISION  
WICHITA KS

Remarks: STEWARD TANK SERVICE. QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

*TD*

Signed

*Richard Williams*

(TECHNICIAN)

AUG 29 2007

*PA*

LARIO OIL & GAS CO.

#5

HENDERSON E.

22-11-18W  
SE NW NE

Contr.

ELLIS

County

E 1981

Comm. 12-20-47

Comp. 1-23-48

IP 2440 BOPD & 13% WTR

DEPTH 0

| Tops  | Depth | Datum  |
|-------|-------|--------|
| AMH   | 1260  | +721.1 |
| HELE  | 3160  |        |
| LANS  | 3210  | -122.9 |
| CONG  | 3457  | -147.6 |
| SLEP  | 3493  | -151.2 |
| ARB   | 3514  | -153.3 |
| T. D. | 3580  |        |

Casing

8" 1273

5" 3582

PERF 31S, 3513-21:  
ACID 600

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

