

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02375-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 34-25S-21E
2750 feet from S Section Line, 2300 feet from E Section Line
Lease Name: PAVLICEK Well #: W 11
County: ALLEN Total Vertical Depth: 680 feet

Operator License No.: 6137
Op Name: ENSMINGER, DONALD & JACK, A GEN
Address: 1446 3000 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	670		
SURF	6.25	20		

\$ 35.00

Well Type: EOR UIC Docket No: E21630.4 Date/Time to Plug: 05/11/2005 8:00 AM
Plug Co. License No.: 6137 Plug Co. Name: ENSMINGER, DONALD & JACK, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DON ENSMINGER Company: ENSMINGER, DONALD & JACK, A Phone: (620) 496-2300

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 680' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE WELL FULL OF CEMENT.

Plugging Proposal Received By: TOM WELSH Witness Type: NONE
Date/Time Plugging Completed: 05/11/2005 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
1" PIPE WAS RAN INTO THE 2" CASING TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 6 1/4" ANNULUS TO 200'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:
INVOICED
DATE 9-10-07
INV. NO 2008060360

RECEIVED
KCC DISTRICT #3
AUG 29 2007
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Plugged through:

District: 03 Signed Clayton P. Titel by SL
(TECHNICIAN)