

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-02374-00-01  
Spot: NENWNE Sec/Twnshp/Rge: 34-25S-21E  
4890 feet from S Section Line, 1770 feet from E Section Line  
Lease Name: PAVLICEK Well #: W 3  
County: ALLEN Total Vertical Depth: 670 feet

Operator License No.: 6137  
Op Name: ENSMINGER, DONALD & JACK, A GEN  
Address: 1446 3000 ST  
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	670		
SURF	6.25	20		

\$ 35.00

Well Type: EOR UIC Docket No: E21630.2 Date/Time to Plug: 05/11/2005 8:00 AM  
Plug Co. License No.: 6137 Plug Co. Name: ENSMINGER, DONALD & JACK, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: DON ENSMINGER Company: ENSMINGER, DONALD & JACK, A Phone: (620) 496-2300

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 670' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE WELL FULL OF CEMENT.

Plugging Proposal Received By: TOM WELSH WitnessType: NONE  
Date/Time Plugging Completed: 05/11/2005 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 6 1/4" ANNULUS TO 200'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED  
DATE 9-10-07  
INV. NO. 2008060360

RECEIVED  
KCC DISTRICT #3  
AUG 29 2007 *BL*  
CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 04 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through:

District: 03

Signed Clayton P. Titel by *BL*  
(TECHNICIAN)

*PK*