

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20445-00-01
Spot: E2SWSW Sec/Twnshp/Rge: 32-8S-23W
660 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WILSON K Well #: 4
County: GRAHAM Total Vertical Depth: 3876 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR	4.5	1609		
PROD	4.5	2000	0	500 SX
SURF	8.625	204	0	160 SX
T1	2.375	1609		

\$ 125.97

Well Type: SWD UIC Docket No: D16127.0 Date/Time to Plug: 08/24/2007 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RICHARD L. WALLGREN, S Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Operator elected to plug with all cement.
Plugging Ordered out 200 sxs 60/40 pozmix - 4% gel with 600# hulls.
Method: Fluid level 100'. Bad casing at 1585'.
Shallow SWD - Cedar Hills.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2007 11:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1250'. Allied pumped 80 sxs 60/40 pozmix - 4% gel with 500# hulls.
Pulled tubing out of the hole. Allied pumped 20 sxs 60/40 pozmix - 4% gel with 100# hulls.
Max. P.S.I. 500#. S.I.P. 400#.
Hooked up to backside - instant 1000#.

Perfs:

Top	Bot	Thru	Comments
1718	1735		
1702	1718		
1685	1701		

INVOICED

DATE 9-10-07
INV. NO. 2008060364

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: MURFIN TANK SERVICE. PLAINS WELL SERVICE.

Plugged through: TBG


District: 04

Signed R. Williams
(TECHNICIAN)

AUG 29 2007

PKR

DANE G. HANSEN TRUST #4 WILSON "K" 32-8-23W
 LOGAN, KANSAS E/2 SW SW
 CONTR C-G DRILLING CO. CTY GRAHAM
 GEOL FRANCIS WHISLER FIELD BRUSH CREEK NW
 E 2337 RB CM 5/1/71 ^{CARD} ISSUED 5/13/71 IP D&A/LANS-KC
 5/7/71
 API 15-065-20,445



SMP	TOPS	DEPTH	DATUM	B 5/8" 204/200sx
ANH		1998	+ 339	DST(1) 3797-3876(LANS)/1', 240' THIN MUD,
TOP		3417	-1080	BHP 899-899#/30", FP 54-162#
HEEB		3633	-1296	
TOR		3660	-1323	NO LOG
LANS		3679	-1342	
TD		3876	-1539	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS