

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-21956-00-00  
Spot: SESESE Sec/Twnshp/Rge: 31-32S-6E  
337 feet from S Section Line, 344 feet from E Section Line  
Lease Name: WERNER UNIT B Well #: 4  
County: COWLEY Total Vertical Depth: 3190 feet

Operator License No.: 5394  
Op Name: ABDERHALDEN, R. R.  
Address: 510 HARDAGE CENTER 100 S MAIN  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3188		75 SX
SURF	8.625	154		64 SX

103.68

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2007 8:00 AM  
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.  
Proposal Rcvd. from: DUANE STOUT Company: R R ABDERHALBEN Phone: (316) 262-3411

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/04/2007 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-11-2007, RIH W/BAILOR COULD NOT GET PASSED 2173'. SANDED BACK @ 2120', DUMP BAILED 5 SXS CEMENT ON TOP. 5-31-2007, SHOT 4-1/2" CASING @ 1775', LAYED DOWN CASING. 6-4-2007, RIH W/TBG @ 345', R.R.A. ESTABLISHED CIRCULATION, MIXED & PUMPED 160 SXS CLASS CEMENT TO SURFCE. CEMENT CIRCULATED. PLUG DOWN 1600 P.M. 06-04- 2007. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
3136	3162		
2738	2743		

INVOICED  
DATE 9-11-07  
INV. NO. 2008060380

Remarks: -096.80775.37.21626, PERFS 2738'-2743', 3136'-3162'

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*Duane Krueger*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 05 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

PKT