

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21152-00-00
Spot: NENWSW Sec/Twnshp/Rge: 19-16S-8W
2223 feet from S Section Line, 4389 feet from E Section Line
Lease Name: BECKER TRUST Well #: 1
County: ELLSWORTH Total Vertical Depth: 3466 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3450		125 SX CMT.
SURF	8.625	284		165 SX CMT.

112.65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2007 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFORATIONS AND CAP WITH 5 SX OF CEMENT. PUMP 35 SX'S AT 900'. PUMP 35 SX'S AT 600' AND CIRCULATE FROM 334' TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 08/20/2007 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 3250' AND CAPPED WITH 5 SX'S OF CEMENT. PULLED PIPE TO 900' AND PUMPED 35 SX'S. PULLED PIPE TO 600' AND PUMPED 35 SX'S OF CEMENT. PULLED PIPE TO 360' AND PUMPED 130 SX'S TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3296	3297		
3286	3287		
3252	3253		

INVOICED
DATE 9-11-07
INV. NO. 2008060383

Remarks: QUALITY WELL SERVICE. TICKET #1478. TOTAL = 200 SX 60/40 POZ 4% GEL (2390' OF PIPE RECOVERED)

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 05 2007

CONSERVATION DIVISION
WICHITA, KS

PAJ