

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-02108-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 2-34S-5E
1347 feet from S Section Line, 4872 feet from E Section Line
Lease Name: BROWN Well #: 3
County: COWLEY Total Vertical Depth: 3096 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S. RIVER ROAD PO BOX 729
OXFORD, KS 67119

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 3065 | 825 | 125 SX |
| SURF | 8.625 | 95 | | 90 SX |

100.62

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/22/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-6-2007, SANDED BACK 50' ABOVE OPEN HOLE @ 3015', DUMP BAILED 6 SXS CEMENT ON TOP. 4-16-2007, SHOT 5-1/2" CASING @ 825', LAYED DOWN 5=1/2" CASING. 5-22-2007, RIH W/TBG @ 240'. BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 95 SXS 60/40 POZMIX @ 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1700, 05-22-2007. CEMENT TICKET #07-571.

Perfs:

INVOICED
DATE 9-11-07
INV. NO. 2008060386

Remarks: -096.85883.37.11721, OPEN HOLE 3065'-3096'.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 05 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

[Handwritten Signature]