

State of Kansas



15-065-02793-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1972
CONSERVATION DIVISION
Wichita, Kansas
4/14/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Schamberger Well No. C-1 Tract-1, Well-#1

Location: SE-SE-SE Sec. 25 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3970' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

251'--8 5/8" surface casing, cement circulated with 175 Sx.
3964'--5 1/2" casing cemented on bottom with 75 Sx. Top of perforations @ 3950'.

Sand well back to 3925' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent