

State of Kansas



15-065-20149-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas
6-10-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Bankoff & Leben,

Complete Address: Drawer #2179, Tulsa, Oklahoma.

Lease Name: Culley Well No. 1

Location: NW-SE-NW Sec. 28 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3885 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1010'.

Circulate hole with heavy mud. Pull DP to 1235' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Decker
Conservation Division Agent