



18-065-20335-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1972
CONSERVATION DIVISION
Wichita, Kansas
9-7-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: 1119 Sherman, Great Bend, Kansas.

Lease Name: Culley Well No. 1

Location: NW-NW-SE Sec. 28 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 4042' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated.

4038'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4010'. Top of perforations @ 3872'.

Sand well back to 3850' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent