



15-065-21674-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Jerry Helberg of Helberg Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Helberg Oil Co.

Complete Address: Box 32, Morland, Mo. 67650

Lease Name: Helberg Well No. 1

Location: SE NW SE Sec. 31 Twp. 8 Rge. 25 (E) (W)

County: Graham Total Depth: 2508'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Helberg was instructed to plug the well as follows:

8 5/8" - 208' SP. cas. w/135 sacks common - 2% Gel - 3% Cal. Cl.
Ordered 160 sacks 50% permix - 4% Gel - 3% Cal. Cl. + 8 5/8" plug.
Spot w/drill stem w/heavy mud between all plugs.
1st plug C. 1350' w/100 sacks, 2nd plug C. 250' w/40 sacks.
3rd plug - solid bridge of hulls & plug C. 40" w/10 sacks.
Circulate 10 sacks in rat hole.

Very truly yours,

Arthur G. Schulz
Conservation Division Agent

STATE CORPORATION COMMISSION
RECEIVED
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas
A-27-82