

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1973  
3-5-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Ziegler Well No. 2

Location: NW-SE Sec. 30 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3980 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

176'--8 5/8" Surface casing, cement circulated.  
3981'--4 1/2" Production casing cemented on bottom with top of cement @  
3150'. Top of perforations @ 3717'.

Push plug to 3700', sand back to 3650' and set 4 Sx. cement with dump  
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks  
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent