

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1972
CONSERVATION DIVISION
Wichita, Kansas
2-7-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gilbert Scheck of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Scheck guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Sutor Well No. 4

Location: NW-NW Sec. 30 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3930' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Scheck was instructed to plug the well as follows:

163'--8 5/8" Surface casing, cement circulated with 125 Sx.
3922'--4 1/2" Production casing cemented with 150 Sx. Well plugged back to 3862. Top of perforations @ 3804'.

Sand well back to 3775' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,


Conservation Division Agent