



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970
CONSERVATION DIVISION
Wichita, Kansas

06-24-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

15-179-20257-00-00

Mr. Bill Draper of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: L. J. Dreiling & Sons, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Feltd Well No. 1

Location: CSW-NE Sec. 31 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 4000' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Draper was instructed to plug the well as follows:

213'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx.
cement thru DP from 1325 to 1000'. Pull DP to 245' and displace 25 Sx.
cement thru DP from 245' to 170'. Pull DP, set bridge @ 40' with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. S. Nichols
Conservation Division Agent