

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. John Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Sutor ^{KCC} J ^{CAP} Well No. 751

Location: Appr. GSW-NW Sec. 32 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3765 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

250'--8 5/8" Surface pipe, cement circulated with 225 Sx.
Dakota section from 1850' to 2030'.

Circulate hole with heavy mud. Pull DP to 2050' and displace 100 Sx.
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1967
9-15-1967
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

H. S. Nichols
Conservation Division Agent