

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 217 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-179-20016-00-00

RECEIVED  
JUN 19 1967  
06-19-1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name: Hansen Fee D <sup>KCC</sup> CAP Well No. D-4

Location: Appr. CS/2-NW Sec. 33 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3850' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

186'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 550' and 25 Sx. cement.

"	"	180' with $\frac{1}{4}$ sk. hulls & 25 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent