



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1973
8-22-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company,

Complete Address: 1016 Union Center, Wichita, Kansas.

Lease Name: Senger Well No. 1

Location: NE-NE-NW Sec. 34 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 4440 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

172'--8 5/8" Surface casing, cement circulated.
3965'--5 5/8" Production casing cemented on bottom with 170 Sx. Well plugged back to 3768'. Top perforations from 3661' to 3658'.

Push plug to 3650', sand back to 3625' and set 5 Sx. cement with dump bailer. Pull 5 5/8" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, Staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent