


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

15-065-  
#-02435-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 19 Twp. 9 Rge. 21 (b) (w)  
Location as "NE/CNW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub>" or footage from lines 330'S 330'W N/4 Corner  
Lease Owner Cities Service Oil Co.  
Lease Name Pricer Well No. 1  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12/28 1950  
Application for plugging filed 12/29 1950  
Application for plugging approved 12/29 1950  
Plugging commenced 12/29 1950  
Plugging completed 12/29 1950  
Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?..... yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top KC 3570 Bottom Arb 3879 Total Depth of Well 3910 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Arbuckle</u>	<u>Dry Hole</u>			<u>8-5/8</u>	<u>280'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Filled with heavy mud 3910' to 280', set plug w/ 15 sacks cement on plug, filled with heavy mud to 280 to 35' of surface, 10 sacks cement to surface.

WELL RECORD

Company Cities Service Oil Company Well No. 1 Farm Priceer  
 Location 330' South and 330' West of N/4 Corner Sec. 19 T. 9 R. 21W  
 Elevation 2349 (2347 cr.) County Graham State Kansas  
 Drlg. Comm. December 16, 1950 Contractor R. W. Mine Drilling Company  
 Drlg. Comp. December 29, 1950 Acid None  
 T. D. 3910' Initial Prod. None - Dry Hole (P. & A. 12-30-50)

CASING RECORD:

8-5/8" 280' cas. 175 sk cas. & 200# C.C.

FORMATION RECORD:

clay	0-10
sand, shale & shells	200
shale, sand & shells	1840
anhydrite	1880
shale, shells & lime	2980
shale & lime	3400
lime	3845
lime & shale	3847
shale & chert	3870
shale	3879
lime	3910 T. D.

Top Lansing	3970'
Top Cherty Conglomerate	3847'
Top Simpson	3874'
Top Arbuckle	3879'
Penetration	21'
Total Depth	3910'

Drill stem test 3880-81 recovered  
 60' slightly oil-cut mud in 30  
 mins., 10 min. SHP 370#.

Drill stem test 3882-87 recovered  
 60' muddy water with some oil in  
 30 mins., 10 min. SHP 370#.

SIFO:	500'	00
	1000'	100
	1500'	170
	2000'	220
	2500'	270
	3000'	300

7-7/8" rotary hole.

**PLUGGING**  
 FILE SEC 19 T 9 R 21W  
 BOOK PAGE 52 LINE 1

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 10 1951