

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21571-00-00
Spot: NENESW Sec/Twnshp/Rge: 27-33S-5W
2156 feet from S Section Line, 1983 feet from W Section Line
Lease Name: TADE Well #: 1
County: HARPER Total Vertical Depth: 4970 feet

Operator License No.: 33649
Op Name: KENNETH W. CORY, LTD.
Address: 6565 W LOOP S STE 780
BELLAIRE, TX 77401

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	203		165 SX CMT.

101.53

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/22/2007 8:00 AM
Plug Co. License No.: 33843 Plug Co. Name: TERRA DRILLING, LLC
Proposal Rcvd. from: MARK CORY Company: KENNETH W CORY LTD Phone: (713) 661-5911

Proposed Plugging Method: 35 SKS TOP OF ARBUCKLE, 35 SKS 950', 35 SKS 650', 35 SKS 250', 25 SKS 60', 15 SKS RH, 10 SKS MH

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/22/2007 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:
THE DRL PIPE WAS RUN IN OPEN END TO TOP OF ARBUCKLE AT 4890', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 250', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE 25 SKS OF CMT WAS CIRC TO SURFACE. THE RAT HOLE WAS CIRC WITH 15 SKS OF CMT. THE MOUSE HOLE WAS CIRC WITH 10 SKS OF CMT.

Perfs:
INVOICED
DATE 1-29-08
INV. NO. 2008061299

Remarks: ALLIED CMT 40/60 POZ 4% GEL
Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 28 2008
CONSERVATION DIVISION
WICHITA, KS

District: 02 Signed _____ (TECHNICIAN)

[Handwritten signature]