

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20735-00-00
Spot: NESWSW Sec/Twnshp/Rge: 16-19S-28W
990 feet from S Section Line, 990 feet from W Section Line
Lease Name: THOMAS Well #: 2
County: LANE Total Vertical Depth: 4710 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4680	0	WITH 225 SX CMT
SURF	8.625	328		WITH 225 SX CMT

153.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2008 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: PATRICK J. GERSTNER Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS. GEL SPACER TO ANHYDRITE. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2008 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

** 400 SX CMT PUMPED DOWN BACKSIDE OF WELL. TEMP. SURVEY WAS COMPLETED. CMT AT 2000'.** PUMPED DOWN 5 1/2" CASING WITH 35 SX CMT MIXED WITH 200# HULLS. DISPLACED WITH 16 SX GEL TO 2000', AND THEN PUMP 200 SX CMT. ON A SLIGHT VACUUM. TIED ONTO BACKSIDE & PUMPED 1/8 BBL & PRESSURED TO 800# & HELD. MEASURED TOC ON 1/28/08 AT 650'. TOP OFF 5 1/2" WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4383	4389		

INVOICED

DATE 2-29-08
INV. NO. 2008061304

RECEIVED
KANSAS CORPORATION COMMISSION


FEB 27 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed Michael Maier
(TECHNICIAN)