

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21505-00-00

Spot: NENW

Sec/Twnshp/Rge: 5-17S-25W

660 feet from N Section Line, 1980 feet from W Section Line

Lease Name: STUTZ

Well #: 2

County: NESS

Total Vertical Depth: 4496 feet

Operator License No.: 31142

Op Name: PETROLEUM PROPERTY SERVICES, IN

Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4470	0	WITH 125 SX CMT
SURF	8.625	252		WITH 175 SX CMT

146.12

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/14/2008 9:00 AM

Plug Co. License No.: 32970

Plug Co. Name: H-D OILFIELD SERVICE, INC.

Proposal Rcvd. from: LEON KUHN

Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed
Plugging
Method:

RUN TBG TO 4400' SPOT 300# HULLS & 30 SX CMT ON BOTTOM. SPOT 30 SX CMT AT 1500'. PERFORATE AT 1200'. PUMP DOWN WITH 80 SX CMT OVER CAPACITY . PUMP 150 SX CMT DOWN 8 5/8".

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/14/2008 3:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4400' & SPOT 30 SX CMT & 300# HULLS. PULLED TBG TO 1580' & PUMPED 50 SX CMT WITH 4% CC. PULLED TBG & WAITED 2 HOURS. PRESSURED CASING TO 500#. PERFORATED @ 1200'. PUMPED 200 SX CMT. CMT DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 45 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF CASING WITH 15 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4470	4496	OH	

INVOICED

DATE

2-29-08

INV. NO.

2008061305

RECEIVED
KANSAS CORPORATION COMMISSION


FEB 27 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Michael Maier

(TECHNICIAN)

Form CR-2/3

PM