

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00112-00-01
Spot: SWSESW Sec/Twnshp/Rge: 25-31S-6W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: JONES Well #: 1 OWWO
County: HARPER Total Vertical Depth: 3925 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3787		175 SX
SURF	8.625	531		

127.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS AND CAP WITH 5 SKS OF CMT. RECOVER CASING .35 SKS 1050, 35 SKS 580, CIRC CMT 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/25/2008 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH AND TO 3570' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS PULLED FROM 2850' TO 1050', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 580', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250', WHERE CMT WAS CIRC TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3654	3658		

INVOICED
DATE 2-29-08
INV. NO. 200 8061306

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008


Remarks: UNITED OIL WELL CEMENTING 40/60 POZ 4% GEL

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed _____



(TECHNICIAN)

