

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-10162-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 31-31S-8W
4973 feet from S Section Line, 2450 feet from E Section Line
Lease Name: WILLIAM L CARR Well #: 1
County: HARPER Total Vertical Depth: 4358 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4358		150 SX
SURF	8.625	160		150 SX

141.64

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/12/2008 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS CAP WITH 5 SKS OD CMT. 35 SKS 1450, 35 SKS 900' CIRC CMT FROM 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 02/12/2008 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK TO 4300' AND CAPPED WITH 5 SKS OF CMT. CASING SQUEEZED FROM 900'-600'. KNIFED A HOLE AT 1450', PUMPED 70 SACK CMT PLUG DOWN 5.5 AND DISPLACED CMT PLUG TO 800'. SHUT IN 750#. RECOVERED 5.5" CASING FROM 550' AND PULLED TO 300'. WHERE CMT WAS CIRC. TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF CMT.

Perfs:

Top	Bot	Thru	Comments
4347	4354		

INVOICED
DATE 2-29-08
INV. NO. 2008061306

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008


Remarks: QUALITY OIL WELL CEMENTING #1787 40/60 POZ 4% GEL

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

