

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-20057-00-02
Spot: SENWSE Sec/Twnshp/Rge: 13-16S-7E
1800 feet from S Section Line, 1672 feet from E Section Line
Lease Name: DOWNES Well #: 2
County: MORRIS Total Vertical Depth: 2793 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
I1	4.5	2250		
PKR		2245		PACKER TYPE AND SETTING DEPTH BAKER SET @ 2245
PROD	5.5	2787		75 SX
SURF	8.625	166		125 SX
T1	2.375	2168		

90.77

Well Type: EOR UIC Docket No: E21532.1 Date/Time to Plug: 01/24/2008 11:00 AM
Plug Co. License No.: 34016 Plug Co. Name: RUF NEK WELL SERVICING AND SUPPLY INC.
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-4081

Proposed Plugging Method: SET C.I.B.P. @ 2,210' & TOP WITH 5 SXS. CEMENT. RUN TUBING TO 220' & CIRCULATE CEMENT TO THE SURFACE INSIDE 4 1/2" CASING & IN 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/13/2008 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SAT C.I.B.P. @ 2,210' & TOPPED WITH 5 SXS. CEMENT. RAN 2 2/3" TUBING TO 247' INSIDE 4 1/2" CASING & CIRCULATES 35 SXS. CEMENT TO THE SURFACE. (MRW) 2/13/2008 - CUT HOLE IN 8 5/8" CASING & RAN 3/4" PLY LINE TO 60' & HIT SOLID. TRIED TO WASH TRHU BUT WAS ON CEMENT. PUMPED 20 SXS. CEMENT TO FILL ANNULUS TO 0' PER J.K. (BJJ)

Perfs:

Top	Bot	Thru	Comments
2787	2808		
2498	2516		
2298	2305		
2291	2295		
2281	2288		

INVOICED

DATE 2-29-08
INV. NO. 2008061300

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY CONSOLIDATED OILWELL SERVICES, LLC. INVOICE #12931 & 12938.

Plugged through: TBG

District: 02

Signed Michael R Wilson
(TECHNICIAN)