

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: KNIGHTON OIL COMPANY, INC.
Address: 1700 N. Waterfront Parkway, Suite 100, Bldg. A
Phone: (316) 630-9905 Operator License #: 5010
Type of Well: ENHR Docket #: E-21,532
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/13/2008 (Date)
by: Mike Wilson & Bill Johnson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Cherokee Depth to Top: 2281 Bottom: 2305 T.D. 2793
Mississippian Depth to Top: 2498 Bottom: 2516 T.D. 2793
Hunton Depth to Top: 2787 Bottom: 2793 T.D. 2793

API Number: 15-127-20057-00-02
Lease Name: Downes
Well Number: 2
Spot Location (QQQQ): C - SE - NW - SE
1650 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 13 Twp. 16 S. R. 7 East West
County: Morris
Date Well Completed: 6/22/74
Plugging Commenced: 1/24/08
Plugging Completed: 2/13/08

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	166'	8 5/8"	166'	none
		surface	2787'	5 1/2"	2787'	none
		surface	2220'	4 1/2"	2220'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1/24/08, safety meeting, ran 2 3/8" tubing to 247', broke circulation, pumped 35 sacks 60/40 poz mix, 4% gel to surface. Pulled out 2 3/8" tubing, top off. 2/13/08, safety meeting, rig up and circulated 3/4" poly pipe down to 60 feet on the backside of 5 1/2' and 8 5/8" casing pumped 50 sacks of 60/40 poz mix, 4% gel to surface. Cement circulated in the cellar.

Name of Plugging Contractor: Consolidated Oil Well Surface Services LLC License #: 31440 33961
Address: P.O. Box 884 Chanute, KS 66720
Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc.
State of Kansas County, Sedgwick, ss.
Earl M. Knighton, Jr (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Earl M. Knighton, Jr.
(Address) 1700 N. Waterfront Parkway, Suite 100, Bldg. A

SUBSCRIBED and SWORN TO before me this 20th day of February, 20 08

[Signature] My Commission Expires: 10/4/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 21 2008
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]