

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shelby Resources, LLC
Address: P.O. Box 1213, Hays, Kansas 67601
Phone: (785) 623 - 3290 Operator License #: 31725
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1-22-2008 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Lime Depth to Top: 3499 Bottom: 3850 T.D. _____
LKC Depth to Top: 4041 Bottom: 4464 T.D. _____
Arbuckle Depth to Top: 4890 Bottom: _____ T.D. 4951

API Number: 15 - 007-23247-0000
Lease Name: Jack Jones
Well Number: #1-33
Spot Location (QQQQ): 139°N + 254'E of app. - NW - NW - SW
2249 2449 Feet from North / South Section Line
584' Feet from East / West Section Line
Sec. 33 Twp. 31 S. R. 14 East West
County: Barber
Date Well Completed: 1-23-2008
Plugging Commenced: 1-23-2008
Plugging Completed: 1-23-2008

KCC
PKT
Per
CP2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		000	262.94 KB	13-3/8"	251.94"	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Heavy mud in the hole. Bottom plug at 4888' with 50 sxs. The second plug at 720' with 50 sxs. The third plug at 270' with 60 sxs. The top plug was at 60' with 50 sxs. and came to surface. Cemented with 60/40 Poz with 4% Gel. Plugged rat hole with 15 sxs. and mouse hole with 10 sxs. Plug down at 10:30 a.m. on 1-23-2008. Allied Cementing ticket #31365. Sterling reported plugging to KCC on 1-24-2008.

Name of Plugging Contractor: sterling Drilling Company License #: 5142
Allied Cementing Co., LLC
Address: 24 S. Lincoln Street, P.O. Box 31, Russell, Kansas 67665-2906.

KCC PKT Per
CP2/3
RECEIVED
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: Shelby Resources, LLC
State of Kansas County, Ellis, ss.

FEB 13 2008

Brian Karlin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

CONSERVATION DIVISION
WICHITA, KS

(Signature) Brian Karlin
(Address) P.O. Box 1213, Hays, Kansas 67601



SUBSCRIBED and SWORN TO before me this 5th day of February, 20 08
Gale D Fischer My Commission Expires: 6-18-2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT