

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10-24-07 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L-KC Depth to Top: 3916' Bottom: 4150' T.D. 4150'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-179-20432-00-00  
Lease Name: Pratt  
Well Number: #4  
Spot Location (QQQQ): SE NW - SW - NW -  
18103431 Feet from  North /  South Section Line  
590' 4844 Feet from  East /  West Section Line  
Sec. 35 Twp. 8 S. R. 29  East  West  
County: Sheridan  
Date Well Completed: 8-29-76  
Plugging Commenced: 11-7-07  
Plugging Completed: 11-8-07

*KCC PPT per OP 2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0'	218'	8 5/8"	218'	0'
Production	Oil, Water	0'	4150'	5 1/2"	4150'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rigged up Murfin and pulled rods and pump. Pulled tubing anchor and MA. Run tubing back open ended to 2500'. Swift on location to plug.  
Pumped 175 sx 60/40 Pozmix w/4% gel and 500# hulls. Pulled tubing to 1600' and pumped 150 sx 60/40 Pozmix w/4% gel and 100# hulls.  
Pulled tubing to 800' and pumped 40 sx 60/40 Pozmix w/4% gel. Cement circulated to surface. Pulled tubing out of hole. Hooked up to surface pipe and pumped 35 sx of 60/40 Pozmix and topped off casing. Plugging complete.

Name of Plugging Contractor: Swift Services, Inc. Murfin Drilling Co Inc License #: 32382 30604 RECEIVED  
KANSAS CORPORATION COMMISSION


Address: P.O. Box 466, Ness City, KS 67560-0466  
Name of Party Responsible for Plugging Fees: Gore Oil Company KCC PPT per

State of Kansas County, Sedgwick, ss. CP 2/3 FEB 27 2008  
CONSERVATION DIVISION  
WICHITA, KS

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack

(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 25th day of February, 20 08  
Rebecca K. Crawford My Commission Expires: 3-20-11  
Notary Public

*Handwritten initials/signature*