

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: ENHR Docket #: E-18,370-00-02
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-24-07 (Date)
by: Steve Bond (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-179-20076-00-01
Lease Name: Pratt Hoxie *KCC PRT PA CP2/3*
Well Number: #3
Spot Location (QQQQ): SE - NW - NW -
4307 Feet from North / South Section Line
4577 Feet from East / West Section Line
Sec. 35 Twp. 8 S. R. 29 East West
County: Sheridan *original*
Date Well Completed: 3-21-68
Plugging Commenced: 11-12-07
Plugging Completed: 11-12-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0'	222'	8 5/8"	222'	0'
Production	Oil, Water	0'	4219'	4 1/2"	4219'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Murfin and pull duo-line tubing and packer from well to plug. Ran tubing back to 2500' and hooked up Swift to plug well. Pumped 200 sx 60/40 Pozmix w/4% gel and 300# hulls. Pulled tubing to 1500' and pumped 50 sx 60/40 Pozmix and cement circulated to surface. Pull rest of tubing and hook to surface. Pump 1 sx, surface was full, pressured to 200 psi. Topped off 4 1/2" casing w/20 sx 60/40 Pozmix. Plugging complete.

Name of Plugging Contractor: murfin Drilling Co Inc
Swift Services, Inc. License #: 32382 30606
Address: P.O. Box 466, Ness City, KS 67560-0466
Name of Party Responsible for Plugging Fees: Gore Oil Company *KCC PRT per CP2/3*
State of Kansas County, Sedgwick, ss. **RECEIVED KANSAS CORPORATION COMMISSION FEB 27 2008**
Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Larry M Jack
(Address) Wichita, KS

SUBSCRIBED and SWORN TO before me this 25th day of February, 20 08
Rebecca K. Crawford My Commission Expires: 3-20-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]