

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC
Address: 125 N Market, #1000, Wichita, KS 67202
Phone: (316) 267-4379 Operator License #: 33168
Type of Well: Gas D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4810 Bottom: 4830 T.D. _____
Mississippian Depth to Top: 4904 Bottom: 4924 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-22214-00-00
Lease Name: Spriggs
Well Number: B-1
Spot Location (QQQQ): _____ - C - SE - SE
660' Feet from North / South Section Line
660' Feet from East / West Section Line
Sec. 32 Twp. 33 S. R. 13 East West
County: Barber
Date Well Completed: 9/30/89
Plugging Commenced: 2/6/08
Plugging Completed: 2/8/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	447'	None
				4 1/2"	4995'	1074' 1128' KCC PTF CP 2/3

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Allied pumped down tubing 15 BW spacer w/250# hulls and spotted 25 sx class A cmt w/50# hulls @ 4748'. Log Tech shot 4 1/2" casing @ 1074' & pulled casing. Allied pumped down tbg 10 sxs gel & spotted 50 sx 60/40/4 pozmix cmt plug @ 809'. Spotted 50 sx 60/40/4 pozmix cmt plug @ 471'. Circulated 20 sxs 60/40/4 pozmix cmt plug from 40' to surface. KCC representative Mr. Steve Pfeifer witnessed & approved plugging operations.

Name of Plugging Contractor: Pratt Well Service, Inc License #: 5893
Address: P.O. Box 847, Pratt, KS 67124

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: Woolsey Operating Co., LLC

FEB 25 2008

State of Kansas County, Pratt, ss.

CONSERVATION DIVISION
WICHITA, KS

Kevin C. Gates, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Kevin C. Gates
(Address) PO Box 847 Pratt, KS 67124

SUBSCRIBED and SWORN TO before me this 15th day of February, 2008

Kathy Wood My Commission Expires: 4-20-10
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202