

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 21 2008

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

CONSERVATION DIVISION
WICHITA, KS

Lease Operator: Globe Operating, Inc.
Address: P.O. Box 12 Gt. Bend, Kansas 67530
Phone: (620) 792-7607 Operator License #: 6170
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: B.J. Hope (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 155-21,404 -00-00
Lease Name: Schmitt
Well Number: 2-10
Spot Location (OOQQ): C - SW - NE - SE
1650 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 10 Twp. 25 S. R. 9 East West
County: Reno
Date Well Completed: _____
Plugging Commenced: 2-5-08
Plugging Completed: 2-6-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	233'	None
				5-1/2"	3996'	2821'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3780' and 5 sacks cement. Cut casing loose @2821', pulled up to 1432', pumped 35 sxs. cement, pulled up to 823', pumped 35 sxs. cement, pulled up to 310' and circulated 170 sxs. cement, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Globe Operating, Inc.
State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 19th day of February, 20 08

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKA