

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20834-00-01  
Spot: NWNESE Sec/Twnshp/Rge: 14-20S-3W  
2294 feet from S Section Line, 852 feet from E Section Line  
Lease Name: JUHNKE Well #: A-1  
County: MCPHERSON Total Vertical Depth: 3730 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3729	540	
SURF	8.625	258		

121.23

Well Type: EOR UIC Docket No: E25424.1 Date/Time to Plug: 02/13/2008 9:30 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: ALAN DEGOOD Company: AMERICAN ENERGIES CORP. Phone: (316) 263-5785

Proposed Plugging Method: SAND PERFS TO 3000' AND CAP WITH 4 SX'S CEMENT. PERFORATE @ 450' AND RUN TUBING THERE AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/13/2008 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2983' AND CAP WITH 4 SX'S CEMENT. CUT OFF CASING @ 540' AND PULL OUT OF HOLE. RUN TUBING TO 450' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

**INVOICED**  
DATE 3-10-08  
INV. NO. 2008061329

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 05 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. UNITED CEMENTING TICKET #8402. 155 SX'S TOTAL

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

*PT*