

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01736-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 19-18S-7W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: GRAY Well #: 4
County: RICE Total Vertical Depth: 3128 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 6 | 3102 | | 250 SX |
| SURF | 10.38 | 204 | | 105 SX |

101.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2008 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2008 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

ORIGINAL GOAL WAS TO MAKE THIS WELL A PRODUCER. GOT PACKER WITH PLUG IN BOTTOM OF, STUCK @ 2800'. UNSCREWED FROM AND PULLED UP 2 JT'S, PUMPED 100 SX'S CEMENT WITH COTTON HULLS. LET SET-RETAGGED @ 2228'. PERFORATE @ 1050', 700', AND 255'. RUN TUBING BACK DOWN TO 1050' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 700' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 255' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3101 | 3111 | | |
| 2953 | 2961 | | |
| 2931 | 2937 | | |
| 2825 | 2832 | | |
| 2808 | 2815 | | |
| 2790 | 2797 | | |
| 2784 | 2787 | | |
| 2755 | 2759 | | |

INVOICED
DATE 3-10-08
INV. NO. 2008061330

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #33413. LOG TEC TICKET 5233.

Plugged through: TBG

District: 02

Signed _____

Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 05 2008

CONSERVATION DIVISION
WICHITA, KS

PA