

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02937-00-00
Spot: NWNESW Sec/Twnshp/Rge: 22-14S-16W
2323 feet from S Section Line, 3696 feet from E Section Line
Lease Name: DREILING B Well #: 3
County: ELLIS Total Vertical Depth: 3417 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3378	0	w/unknown sxs cmt
SURF	8.625	280	0	w/unknown sxs cmt

111.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2008 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: TDI, INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 300# hulls.
Emergency plug with rig over the hole.
Operator elected all cement plug.
Tubing stuck in the hole.
Squeeze jobs: 889' w/200 sxs; 660'-910' w/125 sxs; 588' w/200 sxs; 392'-442' w/250 sxs; 2350'-2645' w/125 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2008 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service shot off tubing at 3000'.
Pulled tubing to 2969'. Allied rigged to tubing - pumped 100 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.
Pulled tubing to 1350'. Allied rigged to tubing - pumped 125 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.
Pulled tubing. Allied rigged to 5 1/2" casing with a swedge - pumped 15 sxs cement.
Max. P.S.I. 650#. S.I.P. 500#.
Dug out 8 5/8" - rigged to backside - pumped 15 sxs cement.
Blew small hole in head. No S.I.P.

Perfs:

Top	Bot	Thru	Comments
2631	3340		

INVOICED
DATE 3-10-08
INV. NO 2008061340

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 05 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #29649.

Plugged through: TBG

District: 04

TD

Signed [Signature]
(TECHNICIAN)

FEB 29 2008

[Signature]


22-14-16W 34
NW NE SW

M. B. ARMER ET AL #3 DREILING B
 Contr. ARMER DRILLING COMPANY, INC. ELLIS County
 E 1882RB Comm. 7-4-50 Comp. 8-25-50 IP 103 BOPD
 PHY POT

Tops	Depth	Datum
ANH	975	+907
HEEB	3070	
TOR	3091	
LANS	3116	-1234
CONG	3365	-1483
ARB	3374	-1492
T.o.D.	3417	

Casing
 8" 280 DP 3394
 5" 3275 ACID 500
 DD 3417
 SWB 10 BO/4 HRS

DREILING POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS