

15-173 -02058-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


11-27-2E

Company. H. H. BLAIR
Farm. Reed No. 1

SEC. 11 T. 27 R. 2E
NW NE NW

Total Depth. 3285'
Comm. 4-25-61 Comp. 5-7-61
Shot or Treated.
Contractor. Red Drlg. Co.
Issued. 8-5-61

County Sedgwick
KANSAS



CASING:
8 5/8" 146' cem w/150 sx.
5 1/2" 3260' cem w/75 sx.

Elevation. 1360' RB

Production. 150 BOPD

Figures Indicate Bottom of Formations.

soil	35
shale	50
lime & shale	110
lime	120
lime & shale brks	290
lime & shale	550
shale & lime	930
shale	1125
shale & lime strks	1490
shale & lime	1630
shale & lime strks	1695
lime & shale	2060
shale & lime	2080
lime	2169
lime & shale	2627
shale & lime	2685
lime & shale	2883
lime & chert	2970
lime	3112
shale	3170
sandy shale & lime	3185
lime	3195
sand	3233
shale & sandy shale	3258
sand	3285
Total Depth	

TOPS: SCOUT	
Lansing	2048
Kansas City	2418
Mississippi	2865
Kinderhook	3119
Viola	3172
Upper Simpson Sand	3194
Lower Simpson Sand	3258
Arbuckle	3283